

# Emittance Exchange at FNPL

Ray Filler for Tim Koeth

November 28<sup>nd</sup>, 2006

# Overview

- Motivation & Overview
- Planned Experiment
- Present Status
  - Beam line design
  - Beam line simulation
  - $TM_{110}$  RF cavity
- Timeline

# Motivation


For FEL applications it is desirable to have a small transverse emittance and high brightness. A longitudinal to transverse emittance exchange has been proposed to achieve this goal. \*

The A0 Photo Injector wishes to show a proof of principle of the emittance exchange.

\* M. Cornacchia, P. Emma, Phys. Rev. ST Accel. Beams 5, 084001 (2002)

# Emittance Exchange

Place a 3.9 GHz  $TM_{110}$  cavity between two dog-leg bends to reduce the momentum spread, thereby reducing the longitudinal emittance. This comes at the cost of introducing a transverse betatron amplitude, thus an increase in transverse emittance. A complete longitudinal to transverse emittance exchange should be observed




# The A0 PhotoInjector

1.5 Cell Cu

Photo Gun

SC 9-Cell Cavity



Nominal operating values for round beam after the 9-cell:


1nC/bunch (typically 10 bunches), nominal energy: 15MeV

$\epsilon_{\text{rms-x}}$  &  $\epsilon_{\text{rms-y}} \sim 3 \text{ mm mrad}$  (measured & from ASTRA)



$\epsilon_{\text{rms-z}} = 23 \text{ mm mrad}$  (from ASTRA)

# A0 Beam Line Layout


15 MeV beam from 9-cell



# Beam Line Layout





# Beam Line Diagnostics



# Twiss Parameters

Beta Functions




# Beam Line Simulations

ASTRA models the beam line from the cathode to the exit of the 9 cell superconducting cavity.

ELEGANT is used from the output of the 9-cell to the dump.

**Emittance Along Beamline**




# Required off axis Longitudinal E-Field

$$\frac{\Delta E}{E_o} \approx \frac{\Delta p}{p} \quad \Delta X_{disp} = D \frac{\Delta p}{p}$$


$$\frac{\Delta E}{\Delta x} = \frac{\partial E}{\partial x} = \frac{E_o}{D}$$

Where  $E_o$  is 15MeV and  $D = 0.330m$

$$\frac{\partial E}{\partial x} = \frac{15MeV}{0.33m} = 45.5keV / mm$$



# 3.9 GHz Power Requirements



80K Q of 36,000 shows 50 kW is fine

(We will be using an existing 3<sup>rd</sup> harmonic input coupler)

An 80 kW 3.9 GHz klystron is being installed in A0 for 3<sup>rd</sup> Harmonic Input Coupler Processing. We will use this for our cavity. Commissioning of the klystron is beginning next week !



# TM<sub>110</sub> Copper Cavity



Half cells were punched from 0.093" copper disks at AES.


Half cells are 1<sup>st</sup> brazed at iris to form dumbbells.

Measure dumbbells & trim to freq.

There is close proximity of one end cell, input coupler, and LN2 tank flange. Therefore these parts were machined from a copper block.




# Measure Stacked Dumbbells




Shows why 5 cells is the upper limit – from mode spacing.

# Bead Pull for Field Flatness



Initial bead pull shows that “solid” input coupler end cell frequency is higher than the others.

5-cell bead pull (not brazed)



# Problems:

Input Coupler End (ICE) machined 0.168mm too short (3MHz too high)


Dumbbells shrinkage due to vacuum leak check (0.022 inches, ~ 10MHz low)

Restored initial length, but frequency did not follow

0.014 inches too much trimmed (3MHz too high)

Dumbbells are physically too long by ~ 1mm.

Cavity profile in question → CMM'ing First data taken Monday:



Four radial profiles taken (90 deg increments) on dumbbell M38-M11.

Needs analysis....

Rest are being scanned.

# Highlights of Time Line

ID	Task_Name	Duration	Start_Date	Finish_Date	Predecessors	Resource_Names
1	<b>Preparation</b>	95.63 days?	Thu 11/16/06	Thu 3/22/07		
7	Remaining Optical design of Beamline	2 wks	Thu 11/16/06	Thu 11/30/06		
9	Design Beamline Vacuum	3 days	Wed 12/6/06	Fri 12/8/06	8	
10	Aquire BPM buttons	4 mons	Mon 11/27/06	Fri 3/9/07		
25	Aquire vacuum components for Tim's Line	6 wks?	Wed 12/6/06	Wed 1/17/07	7,8	
26	Aquire vacuum components for straight line	6 wks?	Wed 12/6/06	Wed 1/17/07	7,8	
27	<b>Installation Phase I</b>	23 days?	Wed 1/17/07	Wed 2/14/07	3,26,20	
28	Break Vacuum	1 day?	Wed 1/17/07	Wed 1/17/07		
31	Modify A0 Beamline	2 wks?	Mon 1/22/07	Fri 2/2/07	29	
32	Install Dogleg Dipole 1	1 day?	Fri 2/2/07	Mon 2/5/07	31	
36	Commission new A0 Beamline	2 days	Thu 1/25/07	Mon 1/29/07	35	
37	<b>Installation Phase II</b>	32 days?	Thu 3/22/07	Tue 5/1/07	12,25,24,7,8,19,20,22	
38	Break Vacuum	1 day?	Thu 3/22/07	Thu 3/22/07		
39	Install RF cavity	3 days	Fri 3/23/07	Tue 3/27/07	38	
41	Close vacuum	3 days	Fri 4/13/07	Tue 4/17/07	40	
44	Commission Tim's Cavity	2 wks?	Tue 5/1/07	Mon 5/14/07	37	
45	Commission new beamline	7 days	Tue 5/1/07	Wed 5/9/07	37	
46	Commission new interlocks	1 day	Tue 5/1/07	Wed 5/2/07	37	
47	Rad Safety Clearance	1 day?	Wed 5/9/07	Thu 5/10/07	46,37,45	
48	Make Measurment	4 mons	Mon 5/14/07	Tue 8/21/07	47,44	
49	Tim Writes Thesis	6 mons	Tue 8/21/07	Thu 1/17/08	48	
50	Tim Graduates	0 days	Thu 1/17/08	Thu 1/17/08	49	